

CONSTRUCTION DETAILS FOR 'GAF ASPHALT SHINGLE ROOFING SYSTEM'


Note: Cobra Intake-Pro must be installed to manufacturer's specifications and installation instructions.

Slots cut in plywood substrate to allow for ventillation. Cobra Intake PRO to be installed over slots, fixed with 45mm clouts

GAF Weatherwatch peel and stick must be used around the air slots

Cobra® IntakePro™ vent system to be used as an option when ridge venting is inadequate / impossible. Min compatible roof pitch = 18.5°

Note: The amount of exhaust ventilation must never exceed the amount of intake ventilation at the soffit or eaves



	DRAWING: SURFACE EXHAUST VENT	DATE: 30 JAN 2021	PAGE: 33.2	
	DETAILS FOR: ASPHALT SHINGLE ROOFING	SCALE: N/A		