



1. IF THE INSULATION COMPRESSIVE STRENGTH IS INSUFFIENT FOR THE EQUIPMENT WEIGHT, INSTALL WOOD UNDER THE EQUIPMENT CARRYING SLEEPER, MATCHING THE HEIGHT OF THE INSULATION.

## EXPOSED WOOD EQUIPMENT SUPPORT DETAIL

Scale: N.T.S.





Notes: This detail is in accordance with the BRANZ Appraisal and CodeMark certification. Please contact us for any required customization. © Ultraguard LTD Technical Support and Advice: Email: technical@gaf.nz Call: 0800 42 33 55 Web: www.gafroofing.co.nz/TPO GAF New Zealand Distributor Drawing Title: GAF EverGuard TPO Roofing

REF: Date: Version: T-800 17/01/2025 A